

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 19, 2011
Date of Addendum: April 7, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
112	75-C075-126	PCC Overlay - Unbonded	Plymouth	STP-S-C075(126)--5E-75	19apr112.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to plan sheet 2:

Add the following to the Estimate Reference Note for Item Code 2123-7450000:

The material necessary for Earth Shoulder Construction shall be supplied by the contractor. Material for shoulder construction is not available in the ditches or backslopes. There is one landowner who has expressed interest in supplying material for shoulders. His name is Mike Nothem. Telephone # 712-539-2522. His site is located 4 miles north of this project on Hwy 3 in the NW corner of section 9, Remsen Twp T-92N, R43W. Other locations will be acceptable per the Standard Specifications for contractor furnished materials.

Replace the Estimate Reference Note for Item Code 2301-1032090 with the following:

PAVEMENT WILL BE AT 9" DEPTH FROM STA. 4+10 – 7+00, 198+75 – 200+56, 202+44 – 204+70, 273+03 – 275+03, 454+08 – 455+08, 456+96 – 457+96, AND 534+08 - 536+08. LOAD TRANSFER BASKETS WILL BE REQUIRED ON 20' CENTERS. A FULL WIDTH PAVER WILL BE REQUIRED FOR ALL MAINLINE PAVING.